BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/01/2015-16 Dated: 04-01-2016

APPROVED TENDER SCHEDULE –'B'

Item No: 42

Name of Work:- Providing chain link fencing to proposed park in Doddabettahalli near Amba Bhavani temple road in Attur ward no 03Yelahanka New Town Sub Division

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri RAMESH Y B	
				Rate	Rate in Words
1	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2015-16	Cum	14.44	250.00	Rupees two hundred fifty only
2	KSRRB 4.1:6Providing and laying in position plain cement concrete mix 1:2:4 with cement @240kgs,with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15cms thick well compacted,in foundation,plinth and cills,including cost of all materials, labour, HOM of machineries, curing complete as per specifications.Specification no 4.1,4.2 (Page.12 & Item No. 4.6)	Cum	17.06	5150.00	Rupees five thousand one hundred fifty only
3	Providing chain link fencing 50mm size of 8 guage properly stretched between rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint (Page No 255 I.No 37.3)	Sqm	448.20	650.00	Rupees six hundred fifty only
4	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials as per specifications.(P.No 255, 37.4)	Mtr	747.00	292.00	Rupees two hundred ninety two only
5	Supplying and fixing M.S. Rectangular Poles made but of 2 equal angles of 65 x 65 x 6 mm welded together and fixed inCC (1:2:4) with 2 Nos. 16 mm dia M. S. hold fast rods each of length 25 cms, including cost of all materials, cutting, bending scafolding etc as per specifications. (P.No 37.2, 255	Rmt	273.00	950.00	Rupees nine hundred fifty only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri RAMESH Y B	
				Rate	Rate in Words
6	KSRB 7.9 : Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and weldin (Page No 32, I.No 7.90)	Kgs	37.80	80.00	Rupees eighty only
7	KSRB-15-17.6: Providing and applying painting two coats (excluding priming coat on new wood surface and / war wood faced surface with enamul paint to give an even shade cleaning of surface of all dirt, dust and forign matte, Sand preparing including cost of maerilals, complete as per specification) (P.No 118. I.No 15.60.1)	Sqm	900.00	78.49	Rupees seventy eight and paise forty nine only
8	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/sand/kanker/Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no 130, PWD SR 2015-16)	Cum	14.44	65.00	Rupees sixty five only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.

Printed on : 08-Dec-2015 16:19